



PURCHASING DEPARTMENT

August 20, 2009

ADDENDUM NO. 3

Addendum to City of Bryan Request for Bid No. 700-DE-0719

“Downtown Phase III – Main Street”

The following changes and clarifications are hereby incorporated into the bid documents and specifications for the Request for Bid package referenced above:

CLARIFICATIONS

- The Bid Proposal & Bid Schedule has duplicate quantities and over run in the following sections:
 - Section C – Item #1 quantity has been revised
 - Section C – Bid Items for temporary pavement repair, concrete pavement repair, and asphalt pavement repair were removed. These were duplicate items. Sections I & J have these bid items.
 - Section I – Bid Item #20 has been removed. This was a duplicate item.
 - The contingency for the project is \$300,000. This amount will be added to the total bid.

END OF ADDENDUM

Bidders are required to acknowledge receipt of addendums in the space provided in the bid documents. It is not necessary to submit copies of the addendums in the sealed bid submitted to the City of Bryan.

CITY OF BRYAN PROPOSAL

Date: _____

Proposal of _____

a corporation organized and existing under the laws of the State of _____;

or a partnership consisting of _____;

or an individual trading as _____:

**TO THE CITY OF BRYAN
BRYAN, TEXAS**

The undersigned hereby proposes to furnish all labor and material, tools, and necessary equipment, for the construction of the project, and to perform the work required for the construction of the said project, at the locations set out by the plans and specifications, in strict accordance with the contract documents.

The undersigned further agree to execute a contract within 5 business days from the date of notice of intent to award this proposal, or within such time as the City of Bryan may determine, and in case the undersigned fails or neglects to appear to execute the contract within the specified time, of which this proposal, the plans, specifications, special provisions and advertisements are a part, the undersigned will be considered as having abandoned it, and the Cashier's Check or Bidder's Bond in the sum of _____

_____(\$ _____) Dollars accompanying this proposal will be forfeited to the City of Bryan, Texas, by reason of such failure on the part of the undersigned.

The undersigned further agree that the proposal guaranty may be retained by the City of Bryan, Texas provided the under-signed is one of the three lowest and most advantageous bidders, and that said proposal guaranty shall remain with the City of Bryan until the contract has been made by the successful bidder; otherwise, proposal guaranty may be obtained from the City Purchasing Manager after forty-eight hours from the time of opening the bids.

The undersigned certify that they are duly authorized to submit this Proposal and that this Proposal is made in good faith without collusion or connection with any other person, persons, partnership, company, firm, association or corporation offering bids on this work, and to do the work for the following bid item unit prices, their associated extended totals and sum of extended totals as listed on the following bid tabulation forms:

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
City of Bryan Job # 700 - DE - 0719
Bid No. 09 - 159

BID SUMMARY

BASE BID.....	\$	
ALTERNATE BID #1 - ROUNDABOUT.....	\$	
ALTERNATE BID #2 - ELECTRICAL.....	\$	
ALTERNATE BID #3 - ELECTRICAL.....	\$	
ALTERNATE BID #4 - ELECTRICAL 24TH STREET.....	\$	
Contingency	\$	300,000.00
TOTAL BID PLUS CONTINGENCY.....	\$	

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
A. GENERAL ITEMS					
1	Mobilization, setup, & project overhead for all equipment, work on project, including related items & appurtenances, complete in place.	1	LS	\$	\$
2	Traffic control, including all signage, temporary paving, cones, striping, buttons and related items & appurtenances, complete in place	1	LS	\$	\$
3	Field locate existing utilities and service lines for construction of the proposed improvements including related items and appurtenances, complete in place	1	LS	\$	\$
4	Continuous access to buildings between 24th Street & 22nd Street including temporary paving, ADA ramps, with related items & appurtenances, complete in place	1	LS	\$	\$
5	Adjust external conduit on building façade where finished pavement has changed, including related items & appurtenances, complete in place	1	LS	\$	\$
6	Relocation of existing gas meters including related items and appurtenances, and coordination with gas company, complete in place	1	LS	\$	\$
7	Covered walkway for temporary access to business along Main Street between 24th Street & 22nd Street, including construction, installation, relocation as needed, removal, related items & appurtenances, complete in place	1	LS	\$	\$
8	City of Bryan Capital Improvements Project sign per detail including related items and appurtenances, complete in place	1	EA	\$	\$
TOTAL SECTION A - GENERAL ITEMS				\$	
B. DEMOLITION ITEMS					
1	Remove and dispose of existing 6" sanitary sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	101	LF	\$	\$
2	Remove and dispose of existing 8" sanitary sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	236	LF	\$	\$
3	Remove and dispose of existing 12" sanitary sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	122	LF	\$	\$
4	Remove and dispose of existing 36" RCP storm sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	363	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
5	Remove and dispose of existing 24" RCP storm sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	408	LF	\$	\$
6	Remove and dispose of existing 18" RCP storm sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	224	LF	\$	\$
7	Remove and dispose of existing 15" RCP storm sewer line with full depth cement stabilized sand backfill including related items and appurtenances, complete in place	40	LF	\$	\$
8	Remove and dispose of existing light poles, bases, and foundation with cement stabilized sand backfill including related items and appurtenances complete in place	26	EA	\$	\$
9	Remove and dispose of existing street signs, bases, and foundations with cement stabilized sand backfill, including related items and appurtenances, complete in place	18	EA	\$	\$
10	Remove and dispose of existing handicap ramps, including related items and appurtenances, complete in place	13	EA	\$	\$
11	Remove and dispose of existing storm sewer inlets including related items and appurtenances, complete in place	8	EA	\$	\$
12	Remove and dispose of existing roadway pavement and base material including related items and appurtenances, complete in place	20,527	SY	\$	\$
13	Remove and dispose of existing sidewalk pavement and base material including related items and appurtenances, complete in place	4,123	SY	\$	\$
14	Remove and dispose of existing trees and root ball including related items and appurtenances, complete in place	8	EA	\$	\$
15	Remove and dispose of existing columns and footings along Main Street including related items and appurtenances, complete in place	9	EA	\$	\$
16	Remove and dispose of existing fence including related items and appurtenances, complete in place	51	LF	\$	\$
17	Remove and dispose of existing gravel pavement and base material including related items and appurtenances, complete in place	929	SY	\$	\$
18	Remove and dispose of existing guardrail and handrail including related items and appurtenances, complete in place	84	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
19	Remove and dispose of existing 4" metal pipe on 24th Street, including related items and appurtenances, complete in place	6	LF	\$	\$
20	Remove and reset existing metal fence on north side of 23rd Street between Main Street and railroad including related items and appurtenances, complete in place	17	LF	\$	\$
21	Remove and dispose of existing wood fence on W. 23rd Street including related items and appurtenances, complete in place.	12	LF	\$	\$
22	Remove and dispose of existing 12" x 12" columns supporting sidewalk on 23rd Street between Main Street and Bryan Avenue including related items and appurtenances, complete in place	6	EA	\$	\$
23	Remove and dispose of existing structures including foundations, plumbing and related items and appurtenances, complete in place	840	SF	\$	\$
24	Disconnect and plug/cap existing 36" RCP storm sewer including related items and appurtenances, complete in place	2	EA	\$	\$
25	Grout fill existing 36" RCP storm sewer including related items and appurtenances, complete in place	48	LF	\$	\$
26	Remove and dispose of existing wooden steps including related items and appurtenances, complete in place	1	EA	\$	\$
27	Grout fill existing abandoned sanitary sewer lines (all sizes) with cap, including related items and appurtenances, complete in place	1542	LF	\$	\$
28	Remove and dispose of existing manhole including base, sections, cone, ring, lid with cement stabilized backfill including related items and appurtenances, complete and in place	5	EA	\$	\$
29	Remove & Dispose of Existing Meter including related fittings, items and appurtenances, complete in place	9	EA	\$	\$
30	Remove and dispose of existing 14" x 16" concrete beam on south side of 23rd Street, between Main Street and Bryan Ave. including related items and appurtenances, complete in place	96	LF	\$	\$
TOTAL SECTION B - DEMOLITION				\$	
C. PAVING AND TRAFFIC ITEMS					
1	Main Street R.O.W. (120') preparation including all dirt work for roadway and sidewalk including related items & appurtenances, complete in place	3.32	STA	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
2	Main Street R.O.W. (100') preparation including all dirt work for roadway and sidewalk including related items & appurtenances, complete in place	13.5	STA	\$	\$
3	24th, 23rd, & MLK R.O.W. (100') preparation including dirt work for roadway & sidewalk including related items & appurtenances, complete in place (ITEM EXCLUDES CEMENT STABILIZED SAND BEHIND RETAINING WALLS)	9.56	STA	\$	\$
4	Alley R.O.W. (25') preparation including all dirt work for roadway & sidewalk including related items & appurtenances, complete in place	9.3	STA	\$	\$
5	8" lime stabilized subgrade with minimum of 6% lime by weight compacted to an apparent dry density of 98% standard proctor density @ optimum moisture content including related items and appurtenances, complete in place	19,308	SY	\$	\$
6	Lime for sub-grade stabilization including related items and appurtenances, complete in place	378	Tons	\$	\$
7	Cement stabilized sand for sub-grade level up, MC-30 Prime Coat and 1 1/2" TYPE D HMA including related items & appurtenances , complete in place (22nd Street at Alley)	48	SY	\$	\$
8	8" Reinforced concrete roadway paving including related items & appurtenances, complete in place	18,237	SY	\$	\$
9	4" Reinforced concrete sidewalk including curb including subgrade preparation and compaction to 98% standard proctor density @ optimum moisture content including related items and appurtenances, complete in place	8,910	SY	\$	\$
10	6" wide concrete high curb including related items & appurtenances, complete in place (23rd Street)	132	LF	\$	\$
11	Brick pavers (double soldier and herringbone patterns) including subgrade preparation, sand, leveling, & compaction including related items & appurtenances, complete in place	2,247	SY	\$	\$
12	Thermoplastic handicap symbol pavement markings (white) including related items & appurtenances	22	EA	\$	\$
13	Thermoplastic TX DOT Railroad crossing pavement markings (white) including related items & appurtenances, complete in place	3	EA	\$	\$
14	24" x 10' Thermoplastic Striping (white) for stop bar including related items & appurtenances, complete in place	110	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
15	Solid Yellow 4" Thermoplastic Striping for pavement markings including related items & appurtenances, complete in place	1666	LF	\$	\$
16	4" Thermoplastic Parking Striping pavement markings (White) including related items & appurtenances, complete in place	5291	LF	\$	\$
17	8" Solid White Thermoplastic Striping for pavement markings including related items & appurtenances, complete in place	196	LF	\$	\$
18	Left Turn Markings with 4" Thermoplastic Striping for pavement markings including related items & appurtenances, complete in place	3	EA	\$	\$
19	Wedge Anchors for future stop sign installation, including related items & appurtenances, complete in place	19	EA	\$	\$
20	Handicap signs for project including bases, poles, brackets, signs, and related items & appurtenances, complete in place	23	EA	\$	\$
21	Do Not Enter Sign, including related items & appurtenances, complete in place	2	EA	\$	\$
22	Type I-C-R Reflective markers including related items & appurtenances, complete in place	21	EA	\$	\$
23	Left Turn Markings with 4" Thermoplastic Striping for pavement markings including related items & appurtenances, complete in place	3	EA	\$	\$
24	Type II-AA Reflective markers including related items & appurtenances, complete in place	28	EA	\$	\$
25	Railroad Crossing sign (W10-1) for project including bases, poles, brackets, signs, including related items & appurtenances, complete in place	2	EA	\$	\$
26	Railroad sign (R15-1) for project including bases, poles, brackets, signs, including related items & appurtenances, complete in place	2	EA	\$	\$
27	Cement stabilized sand for backfill behind retaining walls including related items & appurtenances , complete in place	186	CY	\$	\$
TOTAL SECTION C - PAVING AND TRAFFIC ITEMS				\$	
D. Drainage Items					

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
1	5' curb inlet (front of curb design, RE: Detail) including top, ring, lid, grouting of bottom & storm sewer w/related items & appurtenances, complete in place	23	EA	\$	\$
2	10' curb inlet (front of curb design, RE: Detail) including top, ring, lid, grouting of bottom & storm sewer w/related items & appurtenances, complete in place	4	EA	\$	\$
3	15' curb inlet (front of curb design, RE: Detail) including top, ring, lid, grouting of bottom & storm sewer w/related items & appurtenances, complete in place	3	EA	\$	\$
4	5' X 5' concrete junction box including top, ring, lid, grouting of bottom & storm sewer w/related items & appurtenances, complete in place	4	EA	\$	\$
5	42" Smooth Groove RCP storm sewer w/ full depth cement stabilized backfill including related items & appurtenances, complete in place	39	LF	\$	\$
6	18" HDPE storm sewer w/full depth cement stabilized backfill including related items & appurtenances, complete in place	699	LF	\$	\$
7	24" HDPE storm sewer w/ full depth cement stabilized backfill including related items & appurtenances, complete in place	687	LF	\$	\$
8	30" HDPE storm sewer w/ full cement stabilized backfill including related items & appurtenances, complete in place	504	LF	\$	\$
9	42" HDPE storm sewer w/full depth cement stabilized backfill including related items & appurtenances, complete in place	364	LF	\$	\$
10	48" HDPE storm sewer w/full depth cement stabilized backfill including related items & appurtenances, complete in place	11	LF	\$	\$
11	12" HDPE storm sewer w/full depth cement stabilized backfill including related items & appurtenances, complete in place	198	LF	\$	\$
12	36" HDPE storm sewer w/full depth cement stabilized backfill including related items & appurtenances, complete in place	208	LF	\$	\$
13	6" HDPE perforated storm sewer drain line w/siltation sleeve & cleanouts (RE:Detail) including related items and appurtenances, complete in place	1,045	LF	\$	\$
14	6" HDPE storm sewer drain lines & cleanouts (Re: Detail) w/cement stabilized backfill including related items and appurtenances, complete in place	2,010	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
15	18" HDPE Storm sewer with DURASLOT surface/slotted drain w/ heel guard backfilled with full depth cement stabilized sand including related items & appurtenances, complete in place	627	LF	\$	\$
16	24" HDPE Storm sewer with DURASLOT surface/slotted drain w/ heel guard backfilled with full depth cement stabilized sand including related items & appurtenances, complete in place	80	LF	\$	\$
17	36" HDPE Storm sewer with DURASLOT surface/slotted drain w/ heel guard backfilled with full depth cement stabilized sand including related items & appurtenances, complete in place	50	LF	\$	\$
18	2' X 2' grate inlet box including top, ring, lid, grouting of bottom and storm sewer w/related items and appurtenances, complete in place	1	EA	\$	\$
19	3' X 3' grate inlet box including top, ring, lid, grouting of bottom & storm sewer w/related items & appurtenances, complete in place	2	EA	\$	\$
20	42" Smooth Groove RCP installed by dry bore including related items & appurtenances, complete in place	40	LF	\$	\$
21	Connect existing storm sewer into existing junction box, grout seal wall penetration, including related items & appurtenances, complete in place	3	EA	\$	\$
22	Connect roof drain to existing downspout including related items & appurtenances, complete in place	14	EA	\$	\$
23	HDPE Insert -A-Tee storm sewer connections including related items & appurtenances, complete in place	77	EA	\$	\$
24	4" SDR26 PVC (Heavy Wall) Drain line including connection at building (24th Street) and related items and appurtenance, complete in place	19	LF	\$	\$
TOTAL SECTION D - DRAINAGE				\$	
E. Streetscape/Landscaping Items					
1	Crepe Myrtle "Cherokee" including fertilization, planting/topsoil, mulch, related items & appurtenances, complete in place	27	EA	\$	\$
2	American Elm (Dutch Elm Resistant Variety) 30 gallon/2" minimum with Single central leader including fertilization, planting/topsoil, mulch, related items & appurtenances, complete in place	53	EA	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
3	Live Oak Tree 30 gallon/2" minimum with single central leader including related items & appurtenances, complete in place	23	EA	\$	\$
4	Asian Jasmine (4" pots) including fertilization, planting/topsoil, mulch, related items & appurtenances, complete in place	4770	SF	\$	\$
5	Home run roses (Red) 3 gallon, including related items & appurtenances, complete in place	311	EA	\$	\$
6	Grandma's roses (yellow) 3 gallon, including related items & appurtenances, complete in place	116	EA	\$	\$
7	Structural soil for American Elm and Live Oak tree planting including placement, compaction per manufacturer's recommendations, poly liner, including related items and appurtenances, complete in place	818	CY	\$	\$
8	Top Soil for tree planting (5.5' x 5.5' x 2') including related items & appurtenances, complete in place	190	CY	\$	\$
9	Concrete stairs, ramps to buildings thresholds, landings, support railings, and bases including related items & appurtenances, complete in place	58	SY	\$	\$
10	Brick dumpster enclosure, gate & beam including related items & appurtenances, complete in place	5	EA	\$	\$
11	Dowel on curb for median and alley including related items and appurtenances, complete in place	4,128	LF	\$	\$
12	Bark Mulch for rose planting area, including related items & appurtenances, complete in place	2,404	SF	\$	\$
13	6" Wide, doweled on curb (height varies 2" to 12") along building edge (23rd Street), including related items & appurtenances, complete in place	169	LF	\$	\$
14	6" Bollard with concrete and painting including related items & appurtenances, complete in place (RE: Detail)	7	EA	\$	\$
15	Bike Rack by Highland Products Group LLC, Model 116-1003 (black), including related items & appurtenances, complete in place	2	EA	\$	\$
16	Handrails for ramp at 22nd & Main Streets including related items & appurtenances, complete in place	89	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
17	Guardrail with handrail including related items & appurtenances, complete in place	34	LF	\$	\$
18	CMU retaining wall (smooth grey) including footing, drain, waterproofing of existing brick wall, reinforcement including related items and appurtenances, complete in place	40	LF	\$	\$
19	CMU split face retaining wall (color selected by owner) including footing, drain, waterproofing of existing brick wall, reinforcement including related items and appurtenances, complete in place	60	LF	\$	\$
20	Hydromulch including related items and appurtenances, complete in place (alley Right-of-way)	7382	SF	\$	\$
TOTAL SECTION E - STREETScape/LANDSCAPE				\$	
F. Irrigation Items					
1	Labor, equipment, and material for 2" schedule 40 PVC irrigation line including related items and appurtenances, complete in place	1,430	LF	\$	\$
2	Labor, equipment, and material for 1-1/2" schedule 40 PVC irrigation line including related items and appurtenances, complete in place	46	LF	\$	\$
3	Labor, equipment, and material for 1-1/4" schedule 40 PVC irrigation line including related items and appurtenances, complete in place	53	LF	\$	\$
4	Labor, equipment, and material for 1" schedule 40 PVC irrigation line including related items and appurtenances, complete in place	96	LF	\$	\$
5	Labor, equipment, and material for 3/4" schedule 40 PVC irrigation line including related items and appurtenances, complete in place	1,162	LF	\$	\$
6	Labor, equipment, and material for 1/2" schedule 40 PVC irrigation line including related items and appurtenances, complete in place	3,210	LF	\$	\$
7	Labor, equipment, and material for 4" schedule 40 PVC irrigation sleeve including related items and appurtenances, complete in place	2,800	LF	\$	\$
8	Labor, equipment, and material for Rainbird PESB 1-1/2" Remote Control Valve including related items and appurtenances, complete in place	6	EA	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
9	Labor, equipment, and material for Rainbird 33 DRC 3/4" Quick-Coupling Valve including related items and appurtenances, complete in place	5	EA	\$	\$
10	Labor, equipment, and material for Rainbird RSD-Cex Rain Sensor, including related items and appurtenances, complete in place	1	EA	\$	\$
11	Labor, equipment, and material for Rainbird ESP 12 MC-SS Multistation Controller including related items and appurtenances, complete in place	1	EA	\$	\$
12	Labor, equipment, and material for Febco 850 Backflow Preventer including related items and appurtenances, complete in place	1	EA	\$	\$
13	Labor, equipment, and material for 14 Gauge Wire including related items and appurtenances, complete in place	2,830	LF	\$	\$
14	Labor, equipment, and material for Dri-splice including related items and appurtenances, complete in place	100	LF	\$	\$
15	Labor, equipment, and material for Sprears SCH 80 - 2" ball valve including related items and appurtenances, complete in place	12	EA	\$	\$
16	Labor, equipment, and material for 10" Round Valve Box with lock including related items and appurtenances, complete in place	7	EA	\$	\$
17	Labor, equipment, and material for 12" Round Valve Box with lock including related items and appurtenances, complete in place	5	EA	\$	\$
18	Labor, equipment, and material for 16" Rectangular Valve Box with Lock including related items and appurtenances, complete in place	2	EA	\$	\$
SUB-TOTAL of irrigation items				\$	
F. Electrical items (Labor & Materials Provided by the Contractor)					
1	3" Sch. 40 PVC installed underground per drawings and specifications for TxDOT signal wire, including related items and appurtenances, complete in place	384	LF	\$	\$
2	2 1/2" Sch. 40 PVC, installed underground per drawings and specifications including related items and appurtenances, complete in place	11,162	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
3	2" Sch. 40 PVC, installed underground per drawings and specifications including related items and appurtenances, complete in place	54,562	LF	\$	\$
4	1 1/2" Sch. 40 PVC installed underground per drawings and specifications including related items and appurtenances, complete in place	25,460	LF	\$	\$
5	1 1/4" Sch. 40 PVC installed underground per drawings and specifications including related items and appurtenances, complete in place	7,447	LF	\$	\$
6	1" Sch. 40 PVC installed underground per drawings and specifications including related items and appurtenances, complete in place	238	LF	\$	\$
7	8 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	810	LF	\$	\$
8	6 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	3,696	LF	\$	\$
9	6 AWG bare cable, installed underground per drawings and specifications including related items and appurtenances, complete in place	8,143	LF	\$	\$
10	4 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	9,309	LF	\$	\$
11	3 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	9,552	LF	\$	\$
12	2 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	81,566	LF	\$	\$
13	1 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	32,790	LF	\$	\$
14	1/0 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	61,043	LF	\$	\$
15	2/0 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	75,702	LF	\$	\$
16	3/0 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	22,852	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
17	4/0 AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	12,051	LF	\$	\$
18	300kcmil AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	216	LF	\$	\$
19	350kcmil AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	1,032	LF	\$	\$
20	400kcmil AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	360	LF	\$	\$
21	500kcmil AWG cable, installed underground in Sch. 40 PVC per drawings and specifications including related items and appurtenances, complete in place	792	LF	\$	\$
22	81 festival receptacle installations per "Receptacle Mounting Detail", mounted and wired including, box mountings, conduit, wiring, and receptacles including related items and appurtenances, complete in place	1	LS	\$	\$
23	77 each Christmas light receptacle installations per "Receptacle Mounting Detail", mounted and wired including concrete footings, box mountings, conduit, wiring, and receptacles including related items and appurtenances, complete in place	1	LS	\$	\$
24	38 each event receptacle installations per "Receptacle Mounting Detail", mounted and wired including concrete footings, box mountings, conduit, wiring, and receptacles including related items and appurtenances, complete in place	1	LS	\$	\$
25	Light pole installation per drawings, mounted and wired including concrete footings, box mountings, conduit, wiring, and receptacles including related items and appurtenances, complete in place.	83	EA	\$	\$
26	Concrete electrical service panel foundations, poured in place (1.7 CY ea.) including related items and appurtenances, complete in place	4	EA	\$	\$
27	Concrete operator pads (2 per ESC) adjacent to electrical service cabinet (1 CY ea.) including related items and appurtenances, complete in place	4	EA	\$	\$
28	Electrical service panel, bare, less panelboards and other devices including related items and appurtenances, complete in place.	4	EA	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
29	Panelboards, main service breaker, controllers, wireways, surge arrestors, and metering current transformer cabinet and appurtenances, complete in place for 4 each ESC's.	1	LS	\$	\$
30	Transformer pad 10'x10'x1' (3.7 CY) w/ "Block Out" for conduit per utility company detail	4	EA	\$	\$
TOTAL SECTION F - ELECTRICAL ITEMS				\$	
G. Telephone & Cable TV items (Pedestals provided by Utility Owners. Cables to be provided and installed by owners)					
1	Install Cable TV Pedestal, including related items and appurtenances, including related items and appurtenances, complete in place	8	EA	\$	\$
2	2-2" Scheduled 40 PVC Conduits with pull strings for cable TV service line with natural backfill compacted to 98% ASTM D-698 including related items and appurtenances, complete in place	2,625	LF	\$	\$
3	2-4" Scheduled 40 PVC conduits with pull strings for telephone transmission line with natural backfill compacted to 98% ASTM D-698, including related items and appurtenances, complete in place	1,391	LF	\$	\$
4	1-2" Scheduled 40 PVC Conduits with pull strings for telephone service with natural backfill compacted to 98% ASTM D-698, including related items and appurtenances, complete in place	220	LF	\$	\$
5	1-2" Scheduled 40 PVC Conduits with pull strings for cable service with natural backfill compacted to 98% ASTM D-698, including related items and appurtenances, complete in place	220	LF	\$	\$
6	Install 16"x16" telephone pedestal, including related items and appurtenances, complete in place	9	EA	\$	\$
7	Asphalt pavement repair for telephone conduits including related items and appurtenances, complete in place	135	LF	\$	\$
8	1-4" Scheduled 40 PVC Conduits with pull strings for telephone service line with natural backfill compacted to 98% ASTM D-698 including related items and appurtenances, complete in place	714	LF	\$	\$
TOTAL SECTION G - TELEPHONE & CABLE TV ITEMS				\$	
H. BTU Conduit & Foundation Related Items (BTU to provide and set transformers & switch gears; provide & install related wires)					
1	4" schedule 40 PVC Secondary Conduit with pull strings, including related items and appurtenances, complete in place (Note: Backfill included in Bid Item# H 3.)	1066	LF	\$	\$
2	3-4" Schedule 40 PVC Conduits with pull strings for future with cement stabilized backfill, including related items and appurtenances, complete in place	1668	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
3	Primary Duct Bank (9-4" & 2-2" Schedule 40 PVC, conduits), with Carlon Snap-N-Stac combo spaces spread at manufacturers recommendation with cement stabilized backfill, including related items and appurtenances, complete in place	1841	LF	\$	\$
4	30"x48" communications vault (Armor cast products company or approved equal) including related items and appurtenances, complete in place	7	EA	\$	\$
5	2" Schedule 40 PVC Primary Conduit with pull strings and natural backfill compacted to 98% ASTM D-698, including related items and appurtenances, complete in place	339	LF	\$	\$
6	3'x3'x3.5' Pull boxes (Oldcastle Precast, Inc.) installed at all 90 degree turns of electrical conduit, including related items and appurtenances, complete in place	10	EA	\$	\$
7	Asphalt Pavement Repair, including related items and appurtenances, complete in place	72	SY	\$	\$
8	Transformer Pad including related items and appurtenances, complete in place	10	EA	\$	\$
9	1-4" Schedule 40 PVC Conduit with pull strings for future traffic signals with cement stabilized backfill, including related items and appurtenances, complete in place	152	LF	\$	\$
10	1-2" Schedule 40 PVC Conduit with pull strings for future traffic signals with cement stabilized backfill, including related items and appurtenances, complete in place	152	LF	\$	\$
11	Adjust External conduit on building façade, including related items and appurteanances, complete in place	8	EA	\$	\$
12	24" diameter steel casing (1/2") thickness installed by dry boring, including related items and appurtenances, complete in place	85	LF	\$	\$
TOTAL SECTION H - BTU CONDUIT & FOUNDATION RELATED ITEMS				\$	
I. SANITARY SEWER ITEMS					
1	12" SDR 26 PVC sanitary sewer line with cement stabilized sand backfill, complete and in place, all depths	863	EA	\$	\$
2	8" SDR 26 PVC sanitary sewer line with cement stabilized sand backfill including related items and appurtenances, complete and in place	1746	EA	\$	\$
3	6" SDR 26 PVC sanitary sewer line with cement stabilized sand backfill including related items and appurtenances, complete and in place	189	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
4	4" SDR 26 PVC sanitary sewer line for service with cement stabilized sand backfill including related items and appurtenances, complete and in place	372	LF	\$	\$
5	Standard sanitary sewer manhole including base, sections, cone, rim, lid and related items and appurtenances, complete in place	10	EA	\$	\$
6	Drop sanitary sewer manhole including base, sections, cone, rim, lid and related items and appurtenances, complete in place	3	EA	\$	\$
7	Connect proposed sewer line to existing manhole w/ coring & sealing of wall penetration including related items & appurtenances, complete in place	3	EA	\$	\$
8	Long Sewer Service including fittings, cleanout, with related items & appurtenances, complete in place	16	EA	\$	\$
9	16" diameter steel casing (1/2" thickness) installed by dry boring including related items and appurtenances, complete in place	127	LF	\$	\$
10	16" diameter steel casing (1/2" thickness) installed by open cut including related items and appurtenances, complete in place	40	LF	\$	\$
11	Construct standard concrete manhole on existing sewer line including base, sections, cone, rim, lid, and related items & appurtenances, complete in place	1	EA	\$	\$
12	Long Dual Sewer Service transfer including fittings, cleanout, with related items & appurtenances, complete in place	5	EA	\$	\$
13	Disconnect & cap existing sanitary sewer line including related fittings, items and appurtenances, complete in place	7	EA	\$	\$
14	Temporary Pavement Repair including related items and appurtenances, complete in place	2786	LF	\$	\$
15	Concrete Pavement Repair including related items and appurtenances, complete in place	19	LF	\$	\$
16	Asphalt Pavement Repair including related items and appurtenances, complete in place	8	LF	\$	\$
17	8" SDR 26 PVC sanitary sewer line for services with cement stabilized sand backfill including related items and appurtenances, complete and in place	572	LF	\$	\$
18	Asphalt pavement repair for boring with cement stabilized sand backfill including related items and appurtenances, complete and in place	65	SY	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
19	Asphalt pavement repair for 6' wide trench with cement stabilized sand backfill including related items and appurtenances, complete and in place	456	SY	\$	\$
TOTAL SECTION I - SANITARY SEWER ITEMS				\$	
J. WATER SYSTEM ITEMS					
1	12" C-900 PVC waterline with fittings, cement stabilized backfill, including related items and appurtenances, complete and in place	1954	LF	\$	\$
2	8" C-900 PVC waterline with fittings, cement stabilized backfill, including related items and appurtenances, complete and in place	541	LF	\$	\$
3	6" C-900 PVC waterline with fittings, cement stabilized backfill, including related items and appurtenances, complete and in place	74	LF	\$	\$
4	12" Gate valve and box including related fittings, items and appurtenances, complete in place	15	LF	\$	\$
5	8" Gate Valve including related fittings, items and appurtenances, complete in place	11	EA	\$	\$
6	6" Gate Valve including related fittings, items and appurtenances, complete in place	2	EA	\$	\$
7	Interconnect proposed 12" C-900 PVC waterline to existing 30" concrete steel cylinder waterline with two Smith Blair Dressers (36" min.) including related fittings, items and appurtenances, complete in place	1	EA	\$	\$
8	Interconnect proposed 8" C-900 PVC waterline to existing 8" waterline with fittings including related items and appurtenances, complete in place	1	EA	\$	\$
9	Interconnect proposed 6" C-900 PVC waterline to existing 6" waterline with fittings including related items and appurtenances, complete in place	2	EA	\$	\$
10	Temporary Pavement Repair including related fittings, items and appurtenances, complete in place	2243	LF	\$	\$
11	2" Blow Off Valve in meter box including related fittings, items and appurtenances, complete in place	8	EA	\$	\$
12	Disconnect & cap exist water line including related fittings, items and appurtenances, complete in place	1	EA	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
Addendum #1
City of Bryan Job No. 700-DE-0719
Bid No. 09-159

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
13	Relocate existing water meter including related fittings, items and appurtenances, complete in place	8	EA	\$	\$
14	Short water service transfer including related fittings, items and appurtenances, complete in place	3	EA	\$	\$
15	Short dual water service transfer including related fittings, items and appurtenances, complete in place	1	EA	\$	\$
16	Long water service transfer including related fittings, items and appurtenances, complete in place	4	EA	\$	\$
17	Standard fire hydrant assembly with valve, box, fittings and related items and appurtenances, complete in place	9	EA	\$	\$
18	20" steel casing installed by open cut with spacers for waterline including related fittings, items, and appurtenances, complete in place	20	LF	\$	\$
19	12"X2" tap for irrigation including related items and appurtenances, complete in place	1	EA	\$	\$
20	Concrete pavement repair for water service line beyond limits of new paving including related items and appurtenances, complete in place	14	LF	\$	\$
21	Interconnect proposed 12" C-900 PVC waterline to existing 12" waterline with fittings including related items and appurtenances, complete in place	1	EA	\$	\$
TOTAL SECTION J - WATER SYSTEM ITEMS				\$	
Contingency				\$	300,000.00
TOTAL (SECTIONS A-J).....				\$	

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
City of Bryan Job # 700 - DE - 0719
Bid No. 09 - 159

ALTERNATE BID 1 - ROUNDABOUT AT MAIN/22ND STREET

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
A. ITEMS TO BE DELETED FROM BASE BID					
1	Handicap signs for project including bases, poles, brackets, signs, and related items & appurtenances, complete in place	1	EA	\$	\$
2	American Elm (Dutch Elm Resistant Variety) 30 gallon/2" minimum with Single central leader including fertilization, planting/topsoil, mulch, related items & appurtenances, complete in place	1	EA	\$	\$
3	4" Reinforced concrete sidewalk including curb including subgrade preparation and compaction to 98% standard proctor density @ optimum moisture content including related items and appurtenances, complete in place	115	SY	\$	\$
4	Home run roses (Red) 3 gallon, including related items & appurtenances, complete in place	36	EA	\$	\$
5	Bark Mulch for rose planting area, including related items & appurtenances, complete in place	164	SF	\$	\$
6	Dowel on curb for median including related items and appurtenances, complete in place	62	LF	\$	\$
7	Solid Yellow 4" Thermoplastic Striping for pavement markings including related items & appurtenances, complete in place	94	LF	\$	\$
8	Asian Jasmine (4" pots) including fertilization, planting/topsoil, mulch, related items & appurtenances, complete in place	72	SF	\$	\$
9	24" HDPE Storm sewer with DURASLOT surface/slotted drain w/ heel guard backfilled with full depth cement stabilized sand including related items & appurtenances, complete in place	16	LF	\$	\$
TOTAL SECTION A - ITEMS TO BE DELETED FROM BASE BID..... \$					
B. ITEMS TO BE ADDED TO BASE BID					
1	8" Reinforced concrete roadway paving including related items & appurtenances, complete in place	159	SY	\$	\$
2	8" lime stabilized base with minimum of 6% lime by weight compacted to an apparent dry density of 98% standard proctor density @ optimum moisture content including related items and appurtenances, complete in place	200	SY	\$	\$
3	Lime for sub-grade stabilization including related items and appurtenances, complete in place	4	TONS	\$	\$
4	One way only sign and post including related items and appurtenances, complete in place	4	EA	\$	\$
5	Dashed 4" thermoplastic single striping (white) including related items and appurtenances, complete in place	88	LF	\$	\$

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
City of Bryan Job # 700 - DE - 0719
Bid No. 09 - 159

6	Solid 4" thermoplastic striping (white) including related items and appurtenances, complete in place	146	LF	\$	\$
7	Grandma's roses (yellow) 3 gallon, including related items & appurtenances, complete in place	12	LF	\$	\$
8	Lay down curb including related items and appurtenances, complete in place	126	LF	\$	\$
9	8" C-900 PVC waterline with fittings, cement stabilized backfill, including related items and appurtenances, complete and in place	22	LF	\$	\$
10	18" HDPE Storm sewer with DURASLOT surface/slotted drain w/ heel guard backfilled with full depth cement stabilized sand including related items & appurtenances, complete in place	44	LF	\$	\$
11	2" Schedule 40 PVC Waterline including related items and appurtenances, complete in place	12	LF	\$	\$
12	2" Gate valve and box including related fittings, items and appurtenances, complete in place	1	EA	\$	\$
13	1 1/2" irrigation meter including related items and appurtenances, complete in place	1	EA	\$	\$
14	Brick pavers (double soldier and herringbone patterns) including subgrade preparation, sand, leveling, & compaction including related items & appurtenances, complete in place	54	SY	\$	\$
TOTAL SECTION B - ITEMS TO BE ADDED TO BASE BID..... \$					
TOTAL AMOUNT OF ALTERNATE BID 1..... \$					

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
City of Bryan Job # 700 - DE - 0719
Bid No. 09 - 159

ALTERNATE BID 2 - ELECTRICAL

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
A. ITEMS TO BE ADDED TO BASE BID					
1	Add 81 new festival receptacles (one additional festival receptacle per pole); installation per, mounted and wired including box mountings, conduit, wiring, and receptacles including related items and appurtenances, complete in place. New wiring to be added to current festival receptacle wiring as second hot wire of lengths and size as follows:	1	LS	\$	\$
	8 AWG cable	1,066	LF	\$	\$
	6 AWG cable	4,010	LF	\$	\$
	4 AWG cable	14,336	LF	\$	\$
	3 AWG cable	9,121	LF	\$	\$
	2 AWG cable	4,880	LF	\$	\$
	1 AWG cable	3,252	LF	\$	\$
	1/0 AWG cable	3,945	LF	\$	\$
2	Add 22.3 more cubic feet of concrete to the electrical service panel foundations, poured in place including related items and appurtenances, complete in place.	4	EA	\$	\$
3	Enlarge electrical service cabinet width by three feet to take into account the new panelboards.	4	EA	\$	\$
4	Change electrical service cabinets as follows:				
	ESC3 main circuit breaker from 1200A to 1600A	1	LS	\$	\$
	ESC4 main circuit breaker from 1400A to 1600A	1	LS	\$	\$
	ESC2: F2A from 1200AF/1000AT to 800AF/800AT	1	LS	\$	\$
	ESC2: F2B from 1200AF/1000AT to 1600AF/1600AT	1	LS	\$	\$
	ESC4: F4A from 400AF/400AT to 600AF/600AT	1	LS	\$	\$
TOTAL SECTION A - ITEMS TO BE ADDED TO BASE BID..... \$					

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
City of Bryan Job # 700 - DE - 0719
Bid No. 09 - 159

ALTERNATE BID 3 - ELECTRICAL

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
A. ITEMS TO BE ADDED TO BASE BID					
1	Add new neutral wiring to Phase I event receptacles. Install neutrals for four event receptacles between 26th and 28th streets, two event receptacles between 26th and William J. Bryan, and two event receptacles between William J. Bryan and 24th street.	1	LS	\$	\$
TOTAL SECTION A - ITEMS TO BE ADDED TO BASE BID.....				\$	

BID PROPOSAL
Bid Schedule for Downtown Rehabilitation - Phase III
City of Bryan Job # 700 - DE - 0719
Bid No. 09 - 159

ALTERNATE BID 4 - ELECTRICAL - 24th Street

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
A. ITEMS TO BE ADDED TO BASE BID					
1	7-4" Schedule 40 PVC Conduits with pull strings for future with cement stabilized backfill, including related items and appurtenances, complete in place	155	LF	\$	\$
2	Temporary Pavement Repair including related items and appurtenances, complete in place	105	LF	\$	\$
3	Concrete Pavement Repair including related items and appurtenances, complete in place	50	LF	\$	\$
TOTAL SECTION A - ITEMS TO BE ADDED TO BASE BID.....				\$	

FELONY CONVICTION NOTIFICATION

Any person and/or business entity that enters into a contract with the City of Bryan must give advance notice to the City if any employee or an owner or operator of the business entity has been convicted of a felony. The notice must include a general description of the conduct resulting in the conviction of a felony. The notice must also describe the role that the employee, owner, or operator will perform in executing the contract. The City may require substitution of employees in the performance of the contract.

The City may terminate a contract with a person or business entity if the City determines that the person or business entity failed to give notice as required by this clause, misrepresented the conduct resulting in the conviction, or failed to substitute personnel at City's request.

I, the undersigned agent for the firm named below, certify that the information concerning notification of felony convictions has been reviewed by me and the following information furnished is true to the best of my knowledge.

Vendor's Name:

Authorized Company Official's Name (Printed)

A. My firm is not owned or operated by anyone who has been convicted of a felony nor does it have any employees who have been convicted of a felony:

Signature of Company Official:

B. My firm has employee(s) or is owned or operated by the following individual(s) who has/have been convicted of a felony:

<hr/>	<hr/>
<hr/>	<hr/>

Signature of Company Official:

C. Provide a general description of the conduct resulting in the conviction of a felony.

Signature of Company Official:

D. Describe the role that the person(s) convicted of a felony will play in the performance of the contract.

Signature of Company Official:

CERTIFICATION OF BID

CERTIFICATION and AUTHORIZATION:

RFB #09-159

The undersigned certifies that he has fully read and understands this "Request for Bid" and has full knowledge of the scope, quantity, and quality of the services and materials to be furnished and intends to adhere to the provisions described herein. The undersigned also affirms that they are duly authorized to submit this Bid, that this Bid has not been prepared in collusion with any other Vendor, and that the contents of this Bid have not been communicated to any other Vendor prior to the official opening of this Bid. Additionally, the undersigned affirms that the firm is willing to sign the enclosed Exhibit A, Standard Form of Contract, if awarded the bid.

Signed By: _____ Title: _____

Typed Name: _____ Company Name: _____

Phone No.: _____ Fax No.: _____

E-mail: _____

Bid Address: _____
P.O. Box or Street City State Zip

Order Address: _____
P.O. Box or Street City State Zip

Remit Address: _____
P.O. Box or Street City State Zip

Federal Tax ID No.: _____

Date: _____

The undersigned hereby declares that he has visited the sites and has carefully examined the plans, specifications and contract documents relating to the work covered by his bid or bids, that he agrees to do the work, and that no representations made by the City are in any sense a warranty, but are mere estimates for the guidance of the Contractor.

Upon receipt of notice of intent to award the bid, Contractor will execute a formal contract within five (5) business days, and will deliver a Surety Bond in the amount of 100% of the total bid price for the faithful performance of this contract. The bid security attached, without endorsement, in the sum of (\$ _____) Dollars, is to become the property of the City of Bryan in the event the contract and bond are not executed within the time above set forth, as administrative costs for the delay and additional work caused thereby.

TIME OF COMPLETION : The undersigned agrees to complete the work within Two Hundred Seventy Five (275) working days from the date designated by the Notice to Proceed.

The undersigned further declares that he will provide all necessary tools, and apparatus, do all the work, and furnish all materials, and do everything required to carry out the above mentioned work covered by this proposal, in strict accordance with the contract documents, and the requirements pertaining thereto, for the sum or sums above set forth. Additionally, the undersigned affirms that the firm is willing to sign the City’s Standard Form of Contract as reflected in the specifications, if awarded the contract.

Acknowledgement for Receipt of Addendums:

Addendum Number	_____	Initial	_____
Addendum Number	_____	Initial	_____
Addendum Number	_____	Initial	_____

Respectfully Submitted,

(Signature)

(Address)

(City, State, Zip)

Note: Do not detach bid from other papers. Fill in with ink and submit complete with attached papers.