









BEDDING AND TRENCH FOR DI PIPE & PVC PIPE WITHIN NON-STRUCTURAL OR NEW PAVED AREAS

- ALL BEDDING & INSTALLATION OF DUCTILE IRON PIPE SHALL BE IN ACCORDANCE WITH ANSI/AWWA C150/A21.50
   COMPACTION SHALL BE ATTAINED BY MECHANICAL TAMPING.
- 5. RELATIVE COMPACTION SHALL BE TESTED IN THE PRESENCE OF THE CITY ENGINEER.

  6. DUST RESULTING FROM THE CONTRACTOR'S
- 6. DUST RESULTING FROM THE CONTRACTOR'S
  PERFORMANCE OF THE WORK, EITHER INSIDE OR
  OUTSIDE THE RIGHT-OF-WAY, SHALL BE CONTROLLED
  BY THE CONTRACTOR.

  7. ALL TRENCHES SHALL BE BACK FILLED AND TEMPORARY
  PAVING OR PLATING PLACED AT THE END OF EACH
- PAVING OR PLATING PLACED AT THE END OF EACH WORKING DAY.

  8. SEE "OPEN CUT DETAILS" ST4-00, ST4-01 & ST4-02.
- 9. EVERY 100 FEET PROVIDE A WATER STOP BLOCK COMPOSED OF CEMENT SAND OR NATIVE MATERIAL DEPENDING ON EMBEDMENT. BLOCK SHALL BE 6 FEET IN LENGTH. NO BEDDING SAND IN THIS AREA.

## W4-02

## GENERAL NOTES:

ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SODDED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOCK SOD WILL BE REQUIRED. BARED AREAS SHALL BE SEEDED OR SODDED WITHIN 14 CALENDAR DAYS OF

APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.

ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.

ESTABLISHMENT OF VEGETATION MAY BE A WARRANTY ITEM.

DRAWN BY: C.L.M.

DATE: 01-01-09

SCALE: N T S

APPROVED: W. P. K.

FIGURE:

SHEET 1 OF 1

City of Bryan

The Good Life, Texas Style.

 $\simeq$